

# Rocky Mountain Artificial Turf

226 W 12650 S  
Draper, UT 84020 US  
+1 8018080015  
sales@rmturf.com  
www.artificialturfutah.com



## Estimate

ADDRESS  
Wyatt Dangel  
1435 Lincoln Ave  
Ogden

ESTIMATE 5138  
DATE 11/13/2023

PRODUCT/SERVICE	DESCRIPTION	QTY	RATE	AMOUNT
Playground Package - Go Play Turf	Includes: base work, 4 inches soil removal, 4 inches of hard pack, Go Play Turf 1 inch pile height, 55 oz face weight, infill, and installation	4,779.18	10.9356438	52,263.41
RM55 - Go Play	Go Play Turf - 1 inch pile height, 55 oz face weight	5,538	3.18	
Base Work	Includes 4 inches of soil removal, 4 inches of aggregate material and bringing the boards in	3	3,037.00	
Core Infill	Green Diamond Core Infill (50lb bags)	192	13.55	
Turf Installation, Equipment, and Supplies	Turf Installation- Labor, Equipment, and Supplies	3	3,037.00	
Hard Pack 3/8" - Aggregate Material	3/8" Crushed Gravel per Cubic Yard	59	61.00	
Soil Removal	Soil Removal per Cubic Yards	59	103.00	
Concrete Edges (Treated 2x4)	Treated Perimeter Boards - Per Linear Feet	924.45	3.63	
Artificial Turf Seam Tape	Artificial Turf Seam Tape - Per linear feet	168	0.46	
Artificial Turf Adhesive	Artificial Turf Adhesive	3	239.98	

Ogden Preparatory Academy (OPA)  
Premium Installation  
Go Play Turf Surface  
30x90 ft area + 6 ft walkway

SUBTOTAL	52,263.41
TAX	0.00
<b>TOTAL</b>	<b>\$52,263.41</b>

Accepted By

Accepted Date