



IVY Hill Preparatory Charter

Written by: Carri Edwards



Mr. Parker,

Thank you for allowing us the opportunity to bid on your project.

If you desire any clarification on this proposal, feel free to reach out to me directly.

Sincerely,
Lawrence Fanfair
Manager Partner

Entrance Door Install:

Supply and install 4 metal doors with new 16G metal frame.

NSFRAMEPURCH -

126" x 108" Over All 16G 6 1/8" Welded Frame,

2- 5'0" x 7'0" Openings,

20" Transom, 2" Mullion Each 1

MR13084 VLFEZ 0722B WG6X21 -

2'-6" x 7'-0" RH 161 HM Door,

7" x 22" Vision Lite Kit,

5-3/4" x 20-3/4" - 1/4" Clear Wire glass Each 2

ML13084 VLFEZ 0722B WG6X21

-

2'-6" x 7'-0" LH 161 HM Door,

7" x 22" Vision Lite Kit,

5-3/4" x 20-3/4" - 1/4" Clear Wire glass Each 2

NSED 2110/2170 2110F 446F

626 -

2110F-36- x AU446F x 790 x 791 x 626/630

Flat Bar Exit Device

SVR Fire Rated, 7/0 standard

AU-MO-PB Key-in-Lever (F08)

Satin Chrome Each 2

None - none

626/630

NOR7500689 -

Norton 7500 x SN-134 689 Each 4

AST83 - Astragal 83" Each 2

STFBBI79NRP26D

Stanley FBB179 NRP 4-1/2" x 4-1/2" 26D Hinge. each 12

PE315CN36

Pemko 315CN 36" Door sweep. each 4

NSGL

20" x 60" x 1/4" Clear Tempered Glass. Each 2

GB10

Glazing Bead Cut to size. Inch 320

NSOTH

Detex EAX-500 Gray W-CYL KA. Each 2

Remove existing doors and frames.

Supply and install metal primer and paint on new doors and frames. (color will be chosen by owner)

NOTE. Intercom and buzz-in entry system IS NOT INCLUDED IN THIS PRICE.

RECOMMENDED

Security will be provided if needed for overnight work.

RESPONSIBILITIES

SUPPLIES/EQUIPMENT

AscentHandy will source all materials needed for carrying out this project.

Service Cost

Total Job Cost

\$46,379

SIGN BELOW

To make the following steps as simple as possible:

STEP 1 - Simply type your name in the box below and click "Sign Proposal".

STEP 2 - We will arrange a final call to discuss the remaining details.

STEP 3 - We will set up the best billing arrangements.