



Joe Griffin <jg@encorehighschool.com>

Concrete slab in the big top tent

2 messages

Tim Meyer <timsmeier@verizon.net>
To: Joe Griffen <Jg@encorehighschool.com>

Thu, Mar 25, 2021 at 3:06 PM

Hey Joe, here is the cost to remove 9,408 Sq. Ft. of the assumed 3.5" thick asphalt and replace it with 5" thick 3000 PSI concrete. \$55,500.00

To add # 3 Rebar at 18' O. C. each way add. \$9,400.00

Thanks Tim Meyer

760-559-6739

Joe Griffin <jg@encorehighschool.com>
To: John Griffin <jgriffin@officerteam.com>

Mon, Mar 29, 2021 at 9:30 AM

[Quoted text hidden]

--
JOE GRIFFIN
FACILITIES DIRECTOR
Encore Education Corporation

16955 Lemon Street
Hesperia, CA 92345
760-956-2632
www.encorehighschool.com

CONFIDENTIALITY STATEMENT: This electronic message contains information from Encore Junior Senior High School for the performing and visual arts and may be confidential or privileged. The information is intended solely for the use of the individual(s) or entity(ies) named above. If you are not the intended recipient, be aware that any disclosure, copying, distribution or use of the contents of this message is prohibited. If you have received this e-mail in error, please notify us immediately by telephone at (760) 956-2632 or by e-mail reply and delete this message. Thank you.

N UNO CONSTRUCTION

SANTIAGO NUNO- GENERAL CONTRACTOR
LIC# 1030241

ESTIMATE

ESTIMATE
DATE March 11, 2021

17985 Cherry St.
HESPERIA, CA 92340
Phone 760.265.9681

TO
Joe
Encore High School
Hesperia, CA 92395

JOBSITE 16955 Lemon St.
Hesperia, CA, 92395

Description	Amount
First quote 98' x 96'	
- 9408 S.F. at 4" thick @ \$ 4.25 with wire mesh	\$ 39,984
- Remove and dispose of 9,408 S.F. of asphalt @ \$ 2.00	\$ 18,816
- Bring 50 yards of base for concrete pad	\$ 1,500

Labor and concrete pour and finish is included

concrete pump is not included on bid approximately \$ 2,700

Total **\$60,300.00**


Make all checks payable to N UNO CONSTRUCTION

Payment is due within 7 days.

If you have any questions concerning this invoice, contact SANTIAGO NUNO | 760.265.9681

THANK YOU FOR YOUR BUSINESS!

ESTIMATE



Encore High School
16955 Lemon St
Hesperia, Ca 92345
(760) 269-9089

RB Paving & Landscape

7965 Hemlock Ave
Hesperia, Ca 92345

Phone: (760) 947-4191

Email: ruben271@verizon.net

Fax: (760) 244-7614

Web: www.beltranpavingandlandscape.com

Estimate # 000553
Date 03/07/2021
Business / Lic#856991/C-27/C-
Tax # 12/General B

Description

Total

Concrete	\$71,300.00
----------	-------------

1. Sawcut and Remove approx 9500 sqft of existing asphalt. Load and Haul away to legal dumpsite.
 2. Grade and prep approx 9500 sqft to new contours and elevations.
 3. Place and Compact Road base materials as needed grade and compact base using 5 ton roller.
 4. Install 6x6 wire steel mesh for Concrete strength.
 5. Pour new Concrete slab at 4" by 3500 psi all concrete shall be power trowled ,burn smooth finish and sawcut expansion joint
-

Subtotal \$71,300.00

Total **\$71,300.00**

By signing this document, the customer agrees to the services and conditions outlined in this document.

Encore High School

7 Ft
Chain Link

DRAIN



Existing
Asphalt

EXISTING
PE STORAGE
CIRCUIT

NEW
Concrete
Slab 2" ABOVE
Asphalt

Railcar

STORAGE
Chairs + ASTS

Existing
Asphalt
for
Drain

